

Report No.: AGC01559190708FE03

Page 45 of 64

12. TIME OF OCCUPANCY (DWELL TIME)

12.1. MEASUREMENT PROCEDURE

The EUT shall have its hopping function enabled. Use the following spectrum analyzer settings:

- 1. Span: Zero span, centered on a hopping channel.
- 2. RBW shall be ≤ channel spacing and where possible RBW should be set >> 1 / T, where T is the expected dwell time per channel.
- 3. Sweep: As necessary to capture the entire dwell time per hopping channel; where possible use a video trigger and trigger delay so that the transmitted signal starts a little to the right of the start of the plot. The trigger level might need slight adjustment to prevent triggering when the system hops on an adjacent channel; a second plot might be needed with a longer sweep time to show two successive hops on a channel.
- 4. Detector function: Peak. Trace: Max hold.
- 5. Use the marker-delta function to determine the transmit time per hop.
- 6. Repeat the measurement using a longer sweep time to determine the number of hops over the period specified in the requirements. The sweep time shall be equal to, or less than, the period specified in the requirements. Determine the number of hops over the sweep time and calculate the total number of hops in the period specified in the requirements, using the following equation:

(Number of hops in the period specified in the requirements) = (number of hops on spectrum analyzer) \times (period specified in the requirements / analyzer sweep time)

7. The average time of occupancy is calculated from the transmit time per hop multiplied by the number of hops in the period specified in the requirements.

12.2. TEST SETUP (BLOCK DIAGRAM OF CONFIGURATION)

Same as described in section 8.2

12.3. MEASUREMENT EQUIPMENT USED

The same as described in section 6

12.4. LIMITS AND MEASUREMENT RESULT

Channel	Time of Pulse for DH5 (ms)	Number of hops in the period specified in the requirements	Sweep Time (ms)	Limit (ms)
Low	2.883	20*4	230.640	400
Middle	2.883	20*4	230.640	400
High	2.883	20*4	230.640	400

Note: The π /4-DQPSK modulation is the worst case and recorded in the report.




Attestation of Global Compliance(Shenzhen)Co.,Ltd.


Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,

Xixiang, Bao'an District, Shenzhen, Guangdong, China



TEST PLOT OF LOW CHANNEL









Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,



TEST PLOT OF MIDDLE CHANNEL









Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,



TEST PLOT OF HIGH CHANNEL







Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,



13. FREQUENCY SEPARATION

13.1. MEASUREMENT PROCEDURE

The EUT shall have its hopping function enabled. Use the following spectrum analyzer settings:

- 1. Span: Wide enough to capture the peaks of two adjacent channels.
- 2. RBW: Start with the RBW set to approximately 30% of the channel spacing; adjust as necessary to best identify the center of each individual channel.
- 3. Video (or average) bandwidth (VBW) ≥ RBW.
- 4. Sweep: Auto. e) Detector function: Peak. f) Trace: Max hold. g) Allow the trace to stabilize. Use the marker-delta function to determine the separation between the peaks of the adjacent channels.

13.2. TEST SETUP (BLOCK DIAGRAM OF CONFIGURATION)

Same as described in section 6.2

13.3. MEASUREMENT EQUIPMENT USED

The same as described in section 6.3

13.4. LIMITS AND MEASUREMENT RESULT

CHANNEL	CHANNEL SEPARATION (KHz)	LIMIT (KHz)	RESULT
CH01-CH02	1000	>=25 KHz or 2/3 20 dB BW	PASS

TEST PLOT FOR FREQUENCY SEPARATION



Note: The π /4-DQPSK modulation is the worst case and recorded in the report.



 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,

Xixiang, Bao'an District, Shenzhen, Guangdong, China



14. FCC LINE CONDUCTED EMISSION TEST


14.1. LIMITS OF LINE CONDUCTED EMISSION TEST

F	Maximum RF Line Voltage				
Frequency	Q.P.(dBuV)	Average(dBuV)			
150kHz~500kHz	66-56	56-46			
500kHz~5MHz	56	46			
5MHz~30MHz	60	50			


Note: 1. The lower limit shall apply at the transition frequency.

2. The limit decreases linearly with the logarithm of the frequency in the range 0.15 MHz to 0.50 MHz.

14.2. BLOCK DIAGRAM OF LINE CONDUCTED EMISSION TEST









14.3. PRELIMINARY PROCEDURE OF LINE CONDUCTED EMISSION TEST

- 1. The equipment was set up as per the test configuration to simulate typical actual usage per the user's manual. When the EUT is a tabletop system, a wooden table with a height of 0.8 meters is used and is placed on the ground plane as per ANSI C63.10 (see Test Facility for the dimensions of the ground plane used). When the EUT is a floor-standing equipment, it is placed on the ground plane which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- 2. Support equipment, if needed, was placed as per ANSI C63.10.
- 3. All I/O cables were positioned to simulate typical actual usage as per ANSI C63.10.
- 4. All support equipment received AC120V/60Hz power from a LISN, if any.
- 5. The EUT received DC 5V power from adapter which received AC120V/60Hz power from a LISN.
- 6. The test program was started. Emissions were measured on each current carrying line of the EUT using a spectrum Analyzer / Receiver connected to the LISN powering the EUT. The LISN has two monitoring points: Line 1 (Hot Side) and Line 2 (Neutral Side). Two scans were taken: one with Line 1 connected to Analyzer / Receiver and Line 2 connected to a 50 ohm load; the second scan had Line 1 connected to a 50 ohm load and Line 2 connected to the Analyzer / Receiver.
- Analyzer / Receiver scanned from 150 kHz to 30MHz for emissions in each of the test modes.
- 8. During the above scans, the emissions were maximized by cable manipulation.
- 9. The test mode(s) were scanned during the preliminary test.

Then, the EUT configuration and cable configuration of the above highest emission level were recorded for reference of final testing.

14.4. FINAL PROCEDURE OF LINE CONDUCTED EMISSION TEST

- 1. EUT and support equipment was set up on the test bench as per step 2 of the preliminary test.
- 2. A scan was taken on both power lines, Line 1 and Line 2, recording at least the six highest emissions. Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit. If EUT emission level was less –2dB to the A.V. limit in Peak mode, then the emission signal was re-checked using Q.P and Average detector.
- The test data of the worst case condition(s) was reported on the Summary Data page.



Attestation of Global Compliance(Shenzhen)Co.,Ltd.


Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,

Xixiang, Bao'an District, Shenzhen, Guangdong, China



14.5. TEST RESULT OF LINE CONDUCTED EMISSION TEST

Line Conducted Emission Test Line 1-L



MEASUREMENT RESULT: "TEST fin"

7/26/2019 1 Frequency MHz	Level	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.402000	36.90	10.3	58	20.9	QP	L1	FLO
0.786000	28.50	10.7	56	27.5	QP	L1	FLO
1.374000	26.20	11.5	56	29.8	QP	L1	FLO
2.030000	27.60	11.5	56	28.4	QP	L1	FLO
2.546000	24.90	11.5	56	31.1	QP	L1	FLO
3.222000	26.90	11.5	56	29.1	QP	L1	FLO

MEASUREMENT RESULT: "TEST fin2"

7/26/201 Frequ			Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.40	2000	28.00	10.3	48	19.8	AV	L1	FLO
0.78	6000	20.20	10.7	46	25.8	AV	L1	FLO
1.47	0000	16.20	11.5	46	29.8	AV	L1	FLO
2.03	0000	17.50	11.5	46	28.5	AV	L1	FLO
2.55	4000	14.50	11.5	46	31.5	AV	L1	FLO
3.22	2000	16.20	11.5	46	29.8	AV	L1	FLO




Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,



Line Conducted Emission Test Line 2-N



MEASUREMENT RESULT: "TEST fin"

7/26/2019 10:07AM							
Frequen	4			_	Detector	Line	PE
M	Hz dBμV	dB	dΒμV	dB			
0.2400		10.6	F.0	27.0	0.0		
0.3420	00 32.20	10.6	59	27.0	QP	N	FLO
0.4020	00 35.00	10.3	58	22.8	QP	N	FLO
0.6940	00 27.10	10.4	56	28.9	QP	N	FLO
1.0140	00 25.80	11.4	56	30.2	QP	N	FLO
1.3500	00 26.00	11.5	56	30.0	QP	N	FLO
2.0260	00 24.30	11.5	56	31.7	QP	N	FLO

MEASUREMENT RESULT: "TEST fin2"

7/26/2019 10: Frequency MHz	07AM Level dBμV	Transd dB	Limit dBµV	Margin dB	Detector	Line	PE
0.326000	23.00	10.8	50	26.6	AV	N	FLO
0.402000	27.10	10.3	48	20.7	AV	N	FLO
0.710000	20.00	10.4	46	26.0	AV	N	FLO
0.786000	19.50	10.7	46	26.5	AV	N	FLO
1.358000	16.40	11.5	46	29.6	AV	N	FLO
2.010000	18.40	11.5	46	27.6	AV	N	FLO


RESULT: PASS

Note: All the test modes had been tested, the mode 6 was the worst case. Only the data of the worst case would be record in this test report.



Attestation of Global Compliance(Shenzhen)Co.,Ltd.

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,





APPENDIX A: PHOTOGRAPHS OF TEST SETUP

RADIATED EMISSION TEST SETUP BELOW 1GHZ



RADIATED EMISSION TEST SETUP ABOVE 1GHZ






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



CONDUCTED EMISSION TEST SETUP




CONDUCTED TEST SETUP





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$







APPENDIX B: PHOTOGRAPHS OF EUT

ALL VIEW OF EUT-1



ALL VIEW OF EUT-2





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$

Add: 2/F., Building 2, No.1-4, Chaxi Sanwei Technial Industrial Park, Gushu,



ALL VIEW OF EUT-3




TOP VIEW OF EUT



BOTTOM VIEW OF EUT



 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$







FRONT VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



BACK VIEW OF EUT



LEFT VIEW OF EUT





 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



RIGHT VIEW OF EUT



VIEW OF EUT(PORT)






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



OPEN VIEW OF EUT



VIEW OF BATTERY







 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



INTERNAL VIEW OF EUT-1



INTERNAL VIEW OF EUT-2






 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$



INTERNAL VIEW OF EUT-3



----END OF REPORT----



 $Attestation\ of\ Global\ Compliance (Shenzhen) Co., Ltd.$